# BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2017-18/OW/WORK_INDENT29533

## APPROVED SCHEDULE - B

**STP/BBMP/E-PMT/24/2017-18, Date: 21.02.2018**

**Improvements to Roads and Construction of RCC Drains at maruthi Layout 1st, 2nd and 4th Cross in Ward No. 06 Byatarayanapura Sub Division**

| Sl. No. | Approved Qty. | Description | Unit | Approved Tender Rates of Murali Mohan Y V | |
|---|---|---|---|---|---|
| | | | | In Figures | In Words |
| 1 | 391.14 | KSRRB M300-1. Earth work excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5m, excavated surface levelled and sides neately dressed, the disposed earth to be levelled neatly after breaking of clods complete as per specification. MORTH / Chapter 3 (P.No.142, I.No.19.1 of PW, P&IWTD SR 2016-17) | Cum | 169.27 | Rupees One Hundred Sixty Nine and Twenty Seven Paise Only |
| 2 | 28.35 | Removing & Refixing Stone slabs of drains and Pointing in C.M(1:3) (P.No.25, I.No.5.33 of PW, P&IWTD SR 2016-17) | Sqm | 77.04 | Rupees Seventy Seven and Four Paise Only |
| 3 | 12.15 | Providing granite Slabs of Selected quality roughly dressed and fixed in cement mortor (1:6) including fixing curing etc,. Complete. 7.5cms thick (P.No.25, I.No.5.31.1 of PW, P&IWTD SR 2016-17) | Sqm | 636.58 | Rupees Six Hundred Thirty Six and Fifty Eight Paise Only |
| 4 | 48.48 | KSRB 4-1.2: Providing and laying in position plain cement concrete of mix 1:3:6 with OPC cement @ 220kgs, with 40mm and down size graded granite metal coarse aggregates @ 0.892 cum and fine aggregates @ 0.465 cum, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1, 4.2. (P.No.12, I.No.4.2 of PW,P&IWTD S.R 2016-17) | Cum | 5114.95 | Rupees Five Thousand One Hundred Fourteen and Ninety Five Paise Only |
| 5 | 111.6 | KSRB 4-6.1: Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for foundations, footings, bases of columns for mass concrete including cost of all materials, labour complete as per specifications. Specifcation No. KBS 4.6.2 (P.No.15, I.No.4.28 of PW, P&IWTD SR 2016-17) | Sqm | 234.15 | Rupees Two Hundred Thirty Four and Fifteen Paise Only |
| 6 | 892.8 | KSRB 4-6.4: Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for vertical surfaces such as walls at any thickness, including attached pilasters, buttresses, plinth and string courses cost of all materials, labour complete as per specifications. Specification No.KBS 4.6.2 (P.No.15, I.No.4.31 of PW,P&IWTD SR 2016-17) | Sqm | 297.00 | Rupees Two Hundred Ninety Seven Only |
| 7 | 108.81 | Providing and laying cement concrete using 20mm and downsize granite coarse aggregates and fine aggregates of ready mixed concrete (RMC) for RCC works laid in 15cms thick layers and well compacted vibrating, curing, finishing with necessary cement mortar, with all lead and lifts etc., complete (exclusive of cpost of steel and fabricaton charges) Ready Mixed Cement Concrete M 20 for Raft foundation, Column, Footing, main and secondary beams. (P.No.18, I.No.4.48 of PW, P&IWTD SR 2016-17) | Cum | 5959.33 | Rupees Five Thousand Nine Hundred Fifty Nine and Thirty Three Paise Only |
| 8 | 5.45 | KSRB - 4.9.2: Providing TMT steel reinforcement Fe500 for R.C.C work including straightening, cutting, bending, hooking, palcing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining memebrs wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications. Specification No. KBS 4.6.3. (P.No.17, I.No.4.46.2 of PW, P&IWTD SR 2016-17) | Tone | 70469.95 | Rupees Seventy Thousand Four Hundred Sixty Nine and Ninety Five Paise Only |
| 9 | 30.32 | KSRB 5.2-3: Providing and constructing granite size stone masonry in foundation cement mortor 1:6, stone hammered dressed in courses not less than 20cms high, bond stones at 2m. apart in each course including cost of materaials, labour, curing complete as per specifications. Specifcation No. KBS 5.1.13. (P.No.23, I.No.5.6 of PW, P&IWTD S.R 2016-17) | Sqm | 4244.21 | Rupees Four Thousand Two Hundred Forty Four and Twenty One Paise Only |

Murali Mohan Y.V

Signature of the contractor



Executive Engineer

21/02

| | Proved Qty. | Description | Unit | Approved Tender Rates of Murali Mohan Y V | |
|---|---|---|---|---|---|
| | | | | In Figures | In Words |
| 10 | 6 | KSRB 5-11 : Providing and constructing load bearing wall with solid concrete blocks of size 400x150x200 mm having block density not lessthan 1800 kg/m3 and having a minimum average compressive strength 4.00 N/mm2 confirming to IS 2185 (Part) : 2005 and constructed with CM 1:4 , as per IS 2572:2005 including cost of all materials, labour charegs, scaffolding, curing complete as per specifications. KBS No.5.4 (P.No.25, I.No.5.26.2 of PW, P&IWTD SR 2016-17) | Sqm | 919.40 | Rupees Nine Hundred Nineteen and Forty Paise Only |
| 11 | 52.26 | KSRB 15.1.1 Providing flush pointing to square rubble, course or uncoursed stone masonry with cement mortar 1:3, 20mm deep, after raking joints to depth of 20mm nicely lining, including cost of materials, labour, curing complete as per specifications. (P.No.113, I.No.15.1 of PW, P&IWTD S.R 2016-17) | Sqm | 98.33 | Rupees Ninety Eight and Thirty Three Paise Only |
| 12 | 5.89 | KSRB 4-1.6: Providing and laying in position plain cement concrete of mix 1:2:4 with cement @ 240kgs, with 20mm and down size graded granite metal coarse aggregates @ 0.878 cum and fine aggregates @ 0.459 cum, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1, 4.2. (P.No.12, I.No.4.6 of PW,P&IWTD S.R 2016-17) | Cum | 5515.35 | Rupees Five Thousand Five Hundred Fifteen and Thirty Five Paise Only |
| 13 | 68.04 | Providing and fixing RCC Precast cover slab of 250mm thick for drain in cement concrete M20 using graded granite jelly 20mm and down size with steel reinforcement, including form work, lift charges, curing and concrete finished surfaces on both sides etc, complete and as per drawing and the directions of Engineer in-charge. (Data Rate) | Sqm | 4580.71 | Rupees Four Thousand Five Hundred Eighty and Seventy One Paise Only |

murali mohan Y.V.

**Signature of the Contractor**

21/06

**Executive Engineer**
**Byarayanapura Division**
**BBMP, Bangalore - 92**

21/06